36 Inch Diameter Santa Monica & Venice Sewer To Hyperion

Area A

Grandfather of the Dual Force Main

NOTE
BULKHEAD TO BE CONSTRUCTED BY OTHERS.
SEE SHEET 10 FOR TYPICAL SECTION, MOLE 1 THROUGH 5 & 6.
SEE SHEET 10 FOR SECTION THROUGH BULKHEAD LINE.
DATUM IS MEAN LOWER LOW WATER.
ALL EXISTING SEWER LINES AND SEWER PLANTS TO BE PROTECTED.
EXISTING POWER LINES TO BE PROTECTED UNTIL REMOVED BY OTHERS
ALL EXISTING FUEL, OIL, GAS AND WATER LINES TO BE REMOVED BY OTHERS PRIOR TO DREDGING

PLAN
SCALE 100 0 100 200 300 400 500 FEET

MATCH LINE FOR SHEET NO. 5

U.S. Army Corps of Engineers - Marina del Rey Plans Jun2 1959

REV NO	DATE	REVISION	PEV	JMK	APP
A	5-3-59	Added power line, storm drain, limit of dredging pipe lines & note	F.D.	G.D.W.	R.E.L.
B	1-29-60	Relocated Basin H	G.C.	G.D.W.	R.E.L.
C	6-19-60	Stock pile added, and project line revised	M.D.	J.E.W.	W.J.H.
D	10-27-60	Idled Sewer Line E Plant removal	G.C.	S.F.	G.D.W.
E	8-7-61	Revised end of East Revetment and N. bulkhead - Basin D	W.F.K.	S.F.	G.D.W.

CORPS OF ENGINEERS, U. S. ARMY
OFFICE OF THE DISTRICT ENGINEER
LOS ANGELES, CALIFORNIA

ENGINEER: G.D.W.
DRAWN BY: W.R.W.-F.D.
CHECKED BY: R.E.L.-W.J.H.
SUBMITTED BY:
CHIEF, PLANNING & REPORTS BR.

PLAYA DEL REY INLET AND HARBOR, CALIFORNIA

DREDGING AND REVETMENT
DETAIL PLAN

APPROVAL RECOMMENDED: H.W. Thompson, CHIEF, ENGINEERING DIVISION
APPROVED: C. T. Menton, COLONEL, C. E., DISTRICT ENGINEER
SCALE: AS SHOWN
DATE: JUNE 1959
TO ACCOMPANY OCI - CIV 60-5
SHEET 6 OF 17 SHEETS
FILE NO. (D. O. SERIES) 2260-A REV. E